

Community Development Department

Building & Safety Division

100 Civic Plaza, Dublin, CA 94568 • Ph: (925) 833-6620 • www.dublin.ca.gov

Residential Nailing Schedule

TABLE R602.3(1) FASTENER SCHEDULE FOR STRUCTURAL MEMBERS

ITEM	DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENERa, b, c	SPACING OF FASTENERS	
Roof				
1	Blocking between joists or rafters to top plate, toe nail	4-8d box (2 ½ x 0.113")or 3-8d (2½" × 0.113"); or 3-10d box (3"x0.128");or 3-3"x0.131" nails	Toe nail	
2	Ceiling joists to plate, toe nail	4-8d box (2 ½ x 0.113")or 3-8d (2½" × 0.113"); or 3-10d box (3"x0.128");or 3-3"x0.131" nails	Per joist, toe nail	
3	Ceiling joists not attached to parallel rafter, laps over partitions, face (see Sections R802.3.2, R802.3.2 and Table R802.5.1(9))	4-10d box (3"x0.128");or 3-16d common (3 ½" x 0.162");or 4-3"x0.131" nails	Face nail	
4	Ceiling joist attached to parallel rafter (heel joint) (see Sections R802.3.1 and R802.3.2 and Table R802.5.1(9))	Table R802.5.1(9)	Face nail	
5	Collar tie to rafter, face nail or 11/4" × 20 gage ridge strap to rafter	4-10d box (3"x0.128"); or 3-10d common (3" × 0.148"); or 4-3"x0.131 nails	Face nail each rafter	
6	Rafter or roof truss to plate	3-16d box nails (31/2" × 0.135") or 3-10d common nails (3" × 0.148"); or 4-10d box (3"x0.128"); or 4-3"x0.131" nails	2 toe nails on one side and 1 toe nail on opposite side of each rafter or truss ⁱ	
7	Roof rafters to ridge, valley or hip rafters or roof rafter to minimum 2" ridge beam	4-16d (3¹/₂" × 0.135"); or 2-16d common (3¹/₂" × 0.162"); or 4-10d box (3"x0.128"); or 4-3" x 0.131 nails	Toe nail	
		3-16d box (3 ¹ / ₂ " × 0.135"); or 3-16d common (3 ¹ / ₂ " × 0.148"); or 3-10d box (3"x0.128"); or 4-3" x 0.131 nails	End nails	
Wall				
	Stud to stud (not at braced wall panels)l	16d common (3 ½ " × 0.162")	24" o. c. face nail	
8		10d box (3" x 0.128"); or 3"x 0.131" nails	16" o. c. face nail	
9	(at braced wall panels)	16d box (3 ¹ / ₂ " × 0.135"); or 3" x 0.131" nails	12" o.c.	
		16d common (3 ½" x 0.162")	16" o.c. face nail	
10	Built-up header (2" to 2" header with 1/2" spacer	16d common (3 ¹ / ₂ " × 0.162")	16" o.c. each edge face nail	
	· · · · ·	16d box (3 ½" x 0.135")	12" o.c. each edge face nail	
11	Continuous header to stud	5-8d box (21/2" × 0.113"); or 4-8d common (2 1/2"x 0.131"); or 4-10 box (3" x 0.128")	Toe nail	
12	Top plate to top plate	16d common (3 ½" x 0.162")	16" o.c. face nail	
		10d box (3" × 0.128"); or 3" x 0.131" nails	12" o.c. face nail	
13	Double top plate splice for SDCs A-D ₂ with seismic braced wall line spacing 25'	8-16d common (3¹/₂" × 0.162"); or 12-16d box (3 ½" x 0.135"); or 12-10d box (3" x 0.128"); or 12-3" x 0.131 nails	Face nail on each side of end joist (minimum 24" lap splice length each side of end joint)	
	Double top plate splice for SDCs D_0,D_1 , or D_2 ; and braced wall line spacing 25^{\prime}	12-16d (3 ¹ / ₂ " × 0.135")		
		16d common (3 ½" x 0.162")	16" o.c. face nail	
14	Bottom plate to joist, rim joist, band joist or blocking (not at braced wall panels)	16d box (3 ½" x 0.135"); or 3" x 0.131" nails	12 " o.c. face nail	

ITEM	DESCRIPTION OF BUILDING ELEMENTS	NUMBER AND TYPE OF FASTENER ^{a, b, c} SPACING OF FASTENERS		
15	Bottom plate to joist, rim joist, band joist or blocking (at braced wall panels)	3-16d box (3½" × 0.135"); or 2-16d common (3½" × 0.162"); or 4-3" x 0.131 nails	3 each 16" o.c. face nail 2 each 16" o.c. face nail 4 each 16" o.c. face nail	
16	Top or bottom plate to stud	4-4d box (2 ½" x 0.113"); or 3-16d box (3½" × 0.135"); or 4-8d common (2½" × 0.131"); or 4-10d box (3" x 0.128"); or 4-3" x 0.131 nails	Toe nail	
		3-16d box (3 ½" x 0.135"); or 2-16d common (3 ½" x 0.162"); or 3-10d box (3"x 0.128"); or 3-3" x 0.131 nails	End nail	
17	Top plates, laps at corners and intersections	3-10d box (3" x 0.128"); or 2 – 12D common (3 ½" x 0.162"): or 3-3" x 0.131 nails	Face nail	
18	1" brace to each stud and plate	3-8d box (2 ¹ / ₂ " × 0.113"); or 2-8d common (2 ½"x 0.131"); or 2010d box (3" x 0.128"); or 2 staples 1 ³ / ₄ " ×	Face nail	
19	1" × 6" sheathing to each bearing	3-8d box (2 ¹ / ₂ " × 0.113"); or 2-8d common (2 ½" x 0.131"); or 2-10d box (3" x 0.128"); or 2 staples, 1" crown, 16 ga., 1 ³ / ₄ " long	Face nail	
20	1" × 8" and wider sheathing to each bearing	3-8d box (2¹/2" × 0.113"); or 3-8d common (2 ½" x. 0.131"); or 3-10d box (3" x 0.128"); or 3 staples 1" crown, 16 ga., 1 ¾" long Wider than 1" x 8" 4-8d box (2 ½" x 0.113"); or 3-8d common (2 ½" x 0.131"); or 4 staples, 1" crown, 16 ga., 1³/4" long	Face nail	
Floor				
21	Joist to sill, top plate or girder	4-8d box (2 ¹ / ₂ " × 0.113"); or 3-8d common (2 ½" x 0.131"); or 3-10d box (3"x 0.128"); or 3-3" x 0131" nails	Toe nail	
22	Rim joist, band joist or blocking to sill or top plate (roof application also)	8d box (2 ¹ / ₂ " × 0.113") 8d common (2 ½" x 0.131"); or 10d box (3" x 0.128"); or	4" o.c. toe nail 6" o.c. toe nail	
23	1" × 6" subfloor or less to each joist	3" x 0.131" nails 3-8d box (2¹/₂" × 0.113"); or 2-8d common (2 ½" x 0.131"); or 2-10d box (3" x 0.128"); or 2 staples, 1" crown, 16 ga., 1 ³/₄" long	Face nail	
24	2" subfloor to joist or girder	3-16d box (3 ½" x 0.135") 2-10d common (3 ½ " x 0.162")	Blind or face nail	
25	2" planks (plank & beam - floor & roof)	3-16d box (3½" × 0.135"); or 2-16d common (3½" x 0.162")	At each bearing	
26	Band or rim joist to joist	3-16d common (3 ½" x 0.162") 4-10d box (3" x 0.128"), or 4-3" x 0.131" nails, or 4-3" x 14 ga. staples, 7/16" crown	End nail	
	Built-up girders and beams, 2-inch lumber layers	20d common (4" x 0.192"); or	Nail each layer as follows: 32" o.c. at top and bottom and staggered.	
0.7		10d box (3" x 0.128"); or 3" x 0.131" nails	24" o.c. face nail at top and bottom staggered on opposite sides.	
27		And: 2-20d common (4" x 0.192©; or 3-10d common (3 ½" x 0.128"); or 3-3" x 0.131" nails	Face nail at ends and at each splice	
28	Ledger strip supporting joists or rafters	4-16d box (3 ½" x 0.135"); or 3-16d common (3½" x 0.162"); or 4-10d box (3" x 0.128"); or 4-3" x 0.131 nails	At each joist or rafter, face nail	
29	Bridging to joist	2-10d (3" x 0.128")	Each end, toe nail	

	DESCRIPTION OF BUILDING		SPACING OF FASTENERS					
ITEM	MATERIALS	DESCRIPTION OF FASTENER ^{b, c, e}	Edges (inches) ⁱ	Intermediate supports ^{c, e} (inches)				
Wood structural panels, subfloor, roof and interior wall sheathing to framing and particleboard wall sheathing to framing (see Table R602.3(3) for wood structural panel <i>exterior</i> wall sheathing to wall framing)								
30	3/8" - 1/2"	6d common (2" × 0.113") nail (subfloor wall) ^j 8d common (2 ¹ / ₂ " × 0.131") nail (roof) ^f	6	12 ^f				
31	19/32" - 1"	8d common nail (21/2" × 0.131")	6	12 ^f				
32	11/8" - 11/4"	10d common (3" × 0.148") nail or 8d (2¹/₂" × 0.131") deformed nail	6	12				
Other wall sheathing ^h								
33	1/2" structural cellulosic fiberboard sheathing	11/2" galvanized roofing nail, 7/16" head diameter or 1" crown staple 16 ga., 11/4" long	3	6				
34	²⁵ / ₃₂ " structural cellulosic fiberboard sheathing	13/4" galvanized roofing nail, 7/16" head diameter or 1" crown staple 16 ga., 11/4" long	3	6				
35	¹ / ₂ " gypsum sheathing ^d	11/2" galvanized roofing nail; staple galvanized, 11/2" long; 11/4 screws, Type W or S	7	7				
36	5/8" gypsum sheathingd	1 ³ / ₄ " galvanized roofing nail; staple galvanized, 1 ⁵ / ₈ " long; 1 5/8"screws, Type W or S	7	7				
	Wood structural panels, combination subfloor underlayment to framing							
37	³ / ₄ " and less	6d deformed (2" × 0.120") nail or 8d common (21/2" × 0.131") nail	6	12				
38	7/8" - 1"	8d common $(2^1/2^n \times 0.131^n)$ nail or 8d deformed $(2^1/2^n \times 0.120^n)$ nail	6	12				
39	11/8" - 11/4"	10d common (3" × 0.148") nail or 8d deformed (2 ¹ / ₂ " × 0.120") nail	6	12				

For SI: 1 inch = 25.4 mm, 1 foot = 304.8 mm, 1 mile per hour = 0.447 m/s; 1 Ksi = 6.895 MPa.

- a. Nails are smooth-common, box or deformed shanks except where otherwise stated. Nails used for framing and sheathing connections shall have minimum average bending yield strengths as shown: 80 ksi for shank diameter of 0.192 inch (20d common nail), 90 ksi for shank diameters larger than 0.142 inch but not larger than 0.177 inch, and 100 ksi for shank diameters of 0.142 inch or less.
- b. Staples are 16 gage wire and have a minimum 7/16-inch on diameter crown width.
- c. Nails shall be spaced at not more than 6 inches on center at all supports where spans are 48 inches or greater.
- d. Four-foot by 8-foot or 4-foot by 9-foot panels shall be applied vertically.
- e. Spacing of fasteners not included in this table shall be based on Table R602.3(2).
- f. Where the ultimate design wind speed is 130 mph or less, nails for wood structural panel roof sheathing to gable end wall framing shall be space 6 inches on center. Where the ultimate wind speed is greater than 130 mph, nails for attaching panel roof sheathing to intermediate supports shall be spaced 6 inches on center for minimum 48-inch distance from ridges, eaves and gable end walls; and 4 inches on center to gable end wall framing.
- g. Gypsum sheathing shall conform to ASTM C 1396 and shall be installed in accordance with GA 253. Fiberboard sheathing shall conform to ASTM C 208.
- h. Spacing of fasteners on floor sheathing panel edges applies to panel edge supported by framing members and required blocking and at floor perimeters only. Spacing of fasteners on roof sheathing panel edges applies to panel edges supported by framing members and required blocking. Blocking of roof and floor sheathing panel edges perpendicular to the framing members need not be provided except as required by other provisions of this code. Floor perimeter shall be supported by framing members or solid blocking.
- The fastener schedule provides minimum nailing requirements (i.e. size, spacing) for connecting building elements used in wood framed construction. For wood structural panels, both edge nailing and intermediate (field) nailing are specified. In addition to the nailing for wood structural panels, fasteners are specified for gypsum wall sheathing, cellulosic fiberboard wall sheathing and combination subfloor underlayment.